Date: July-24-19
To: Bidders for Norfolk County Bid No. CS-PR-19-15
Simcoe Kinsmen Park – Rubberized Ground Surface
From: Becky Young, Purchasing Agent, Corporate Support Services
purchasing@norfolkcounty.ca
Subject: Addendum No. 1 (3 pages)

ADDENDUM No. 1

This Addendum shall form part of the Contract Documents.

The Bidders should acknowledge receipt of this Addendum on the Submission Form – Appendix A.

1. **Question:**
   You are asking for concrete curbing within the document. The rubber can be installed without curbing which is a cost savings and still accessible. Rubber can be installed at a 45 degree angle below the existing grade. The final grade would be what is existing on site. (grass?)

   Answer:
   The rubber surface will require a concrete curb system with border, minimum 6 inches wide.

   Delete:
   Section 4.9 Deliverables

   Replace With:
   Revised Section 4.9 Deliverables

   4.9 Deliverables

   The Corporation of Norfolk County invites bid submissions based on the delivery and install of rubberized ground surface material at the Simcoe Kinsmen Park located in Simcoe, Ontario at 255 Head Street North.

   This project is made possible through grant money specifically to address accessibility as well as municipal funds and the timing is critical to grant

Accessible formats and communication supports available upon request.

requirements. The total budget for this RFT is a maximum of $130,000. The installation needs to be complete by November 15, 2019.

Project Details

A. It is the responsibility of the successful bidder to provide fencing for security purposes over the duration of the project.

B. Remove and dispose of existing wood fibre surfacing. All site preparation including excavation, drain layer and surfacing will be completed by the successful bidder.

C. Install rubberized ground surface material:

i. provide rubberized surface to replace existing size and shape of wood fibre surfacing;
ii. thickness must be in accordance with the max fall height of the play structure, the max fall height is 115 inches;
iii. the colour will be determined at the time of award;
iv. must be bacteria, fungal and UV resistant;
v. must meet ASTM F1292 standard;
vi. must ensure proper base material and preparation prior to installing the rubber base; and
vii. the rubber surface will require a concrete curb system with border, **minimum 6 inches wide**;
viii. poured-in-place or tile acceptable;

D. The successful bidder will be responsible to leave the site in the same condition it was prior to the commencement of the project. This shall include sodding all ground areas disturbed during the supply and delivery of work as defined in this document. Restorations shall be to the satisfaction of the County.

E. Must also comply with the Design of Public Spaces Standard under the Integrated Accessibility Standards Regulation (O. Reg. 191/11):

Design of Public Spaces Standard – Outdoor Play Spaces – incorporate accessibility features, such as sensory and active play components, for children and caregivers with various disabilities into the design of outdoor play spaces; and ensure that outdoor play spaces have a ground surface that is firm, stable and has impact attenuating properties for injury prevention and

Accessible formats and communication supports available upon request.

sufficient clearance to provide children and caregivers with various disabilities the ability to move through, in and around the outdoor play space.

F. Bids shall include any manufactured components, freight and installation.

End of Addendum

Accessible formats and communication supports available upon request.